Dated 25th October 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 24th November 1930 (5 P.M.), for "Restoring Bommenahalli Dasankatte Tank, [Registered No. 207 of Madhugiri Taluk, Tumkur District." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of December 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government promissory notes, as earnest money and be superscribed "Tender for Restoring Bommenahalli Dasankatte Tank, Registered No. 207 of Madhugiri Taluk, Tumkur District" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore, who does dot bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

9. Within eight days of the acceptance of the tender of the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and earnest money forfeited.

The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer, will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lump sum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.

Abstract estimate for Restoring Bommenahalli Dasankatte Tank, Registered No. 207 of Madhugiri Taluk, Tumkur District.

Sl. No.	Items of work	Quantity	Per	Rate in figures	Rate in words	Cost
				Rs. a. p.		
	Bund at R. L. 56·00.					
1	Jungle clearing and removing trees, etc.	17	Grade			
2	Cutting grips on the top of bund to receive fresh earth	2,310	R.yd.			
3	Earth work to bund including lead and lift with watering and tamping	2,740	C.yd.			
4	Turfing	4,986	S.yd.			
5	Providing and fixing new grade stones with figures cut and painted ...	17	Each			
6	Providing Register No. stones with figures cut and painted ...	1	,,			
7	Providing B. M. stones with figures cut and painted	2	,,			
8	Providing Index stones with figures cut and painted	17	,,			
9	Providing gauge stone with figures cut and painted	1	,,			
	Breach filling.					
1	Clearing silt in the bed of breach ...	295	C.yd.			
2	Cutting grips and steps and trench in foundations	Lump	sum			
3	Filling in breach with selected soil including watering and tamping and ½ furlong lead for gravel ...	1,722	C.yd.			
4	Filling in breach with quantity available from draft clearing ...	1,264	,,			
5	Earthwork excavation	121	,,			
6	Putting in puddle into trenches ...	490	,,			
7	New rough stone work	472	,,			
8	Turfing	1,144	S.yd.			
9	Burnt brick in surki mortar ...	400	C.ft.			
10	Stepping rock in foundations ...	Lump	sum			
	Waste weir at R. L. 51·00.					
1	Clearing draft and approach ...	1,264	C.yd.			
2	Concrete in surki mortar ...	522	C.ft.			
3	Burnt brick in surki mortar ...	544	,,			
4	Plastering with surki mortar ...	7·94	Sqr.			
5	Burnt stone slabs dressed 6″ thick ...	263	S.ft.			
6	New rough stone work	156	C.yd.			
7	Earthwork to training bank including lead and lift with watering and tamping	200	,,			
8	Turfing	250	S.yd.			
	Sluice at R. L. 45·00.					
1	Cut opening the bund	130	C.yd.			
2	Concrete in surki mortar ...	251	C.ft.			
3	Burnt brick in surki mortar ...	290	,,			
4	Plastering with surki mortar ...	6·71	Sqr.			
5	Burnt stone slabs dressed 6″ thick ...	360	S.ft.			
6	Cutting and drilling holes ...	3	Each			
7	Providing and fixing plug and rod with locking arrangements ...	1	,,			
8	Earthwork cutting to lead off channel.	Lump	sum			
9	Refilling the earth with watering, etc.	120	C.yd.			
10	Blocking the old pipe damaged sluice	Lump	sum			
11	Rough stone pitching	6	C.yd.			

A. TANDONI RAO,
Executive Engineer.